


RBSP
Radiation Belt Storm Probes

RBSP Magnetics: Swing Test Analysis

**Haje Korth, Nelli Mosavi, Carl Herrmann
JHU/APL**



Outline




- Purpose and results
- Analysis assumptions and most significant tests
- Test setup and execution
- Data analysis of swing and spin tests
- Spacecraft magnetic moments and conclusions





Purpose and Results



- **Purpose of magnetic swing tests:**


- To verify that all sources of the spacecraft DC magnetic field are accounted for.
- To estimate the spacecraft magnetic moment.
- To verify that the static spacecraft magnetic field at the EMFISIS DC Magnetometer sensors is less than 5 nT in orbit.
- To verify that no magnetic contamination occurred during shipment of the spacecraft to Astrotech.

- **Results of test data analysis:**

- The latch valves and compensation magnets are the only significant sources of the spacecraft static magnetic field.
- The dipole moments in SC coordinates are $[-0.82, 0.14, 0.99]$ and $[-0.83, 0.25, 0.93]$ Am^2 for RBSP A and B, respectively, and have not changed since the spacecraft left APL.
- The magnetic field magnitudes at the locations of the EMFISIS DC Magnetometer sensors are 2.96 and 2.90 nT for RBSP A and B, respectively, demonstrating that the requirement limit of 5 nT was met for both spacecraft.



Analysis Assumptions



- **Spacecraft magnetic field sources:**


- All hardware was carefully selected and tested for remanent magnetization. Components without a non-magnetic option were demagnetized prior to installation.
- PCB layouts were designed to minimize current loops.
- All instrument and subsystem boxes underwent powered and unpowered magnetics testing to screen for remanent and current-induced magnetic fields.
- Solar panels were back-wired to create magnetic field compensating current loops and generated magnetic fields were verified by operating the panels in reverse-bias mode.

- **Analysis assumptions:**



- The latch valves and cancellation magnets are the only significant sources of the spacecraft magnetic field.
- The superposition of magnetic fields from individual sources can be approximated by a dipole moment.
- The location of the dipole moment is given by the average location of its sources.



Magnetics Test: Latch Valve Assembly




- Latch valves employ magnets in the design.
- Magnetic moments of 3 latch valves mounted side-by-side add constructively.
- Net moment points radially outward, to be cancelled by a compensation magnet.
- Radial magnetic field at 1 m distance is 440 nT, requiring a cancellation magnet with moment 2.2 Am^2 .
- Safe-distance requirement for mounting of cancellation magnet compromised the potential for perfect cancellation.





	@ 2 m			@ 3.5 m		
	Bx [nT]	By [nT]	Bz [nT]	Bx [nT]	By [nT]	Bz [nT]
Assembly 1	17.5	53.0	5.5	3.3	10.1	1.0
Assembly 2	10.0	55.0	2.0	3.6	10.5	0.4



Magnetics Test: Solar Panels




- Panels powered by a reverse-bias square-wave current with 0.4 A amplitude (flight-like), magnetic field measured in plane of panel at 0.5 and 1 m distance.
- All panels measured <1 nT (below noise level) in this configuration.
- Cross check: Amplitudes >200 nT were observed 10 cm beneath panel.







Swing Test Setup




- Spacecraft suspended from crane.
- Two sets of magnetometers placed on opposite sides of spacecraft; closest distance to SC at rest: 1 m.
- Magnetometers were configured in gradiometer mode to separate use signal from background variations.
- SC swung toward magnetometers for 5-10 periods with an initial deflection of 60 cm.
- Signal amplitudes up to 100 nT with <10% contribution from crane.
- Rotation of spacecraft used to verify location of most significant source.






Swing Test in Action






Spin Test




- To verify at the system level that the latch-valve and compensations magnets present the only significant source of magnetic fields, the magnetic field was mapped for a 360° rotation of the spacecraft.





Swing Test Analysis



- Rotation test showed largest magnetic field magnitude near Panel 0, consistent with the location of the latch-valve assembly.
- Here: Analysis of SC A with Panel 0 toward APL test magnetometers.

- Fit observations with function:

$$B(t) = k/r(t)^3 + c$$

- Compute magnetic moment:



$$M_x = k_x/200 = 0.68 \text{ Am}^2$$

$$M_y = k_y/100 = 0.48 \text{ Am}^2$$

$$M_z = k_z/100 = 0.99 \text{ Am}^2$$


- Rotate into SC coordinates:

$$\vec{M} = [-0.82, 0.14, 0.99] \text{ Am}^2$$





Spacecraft Magnetic Moments



- Magnetic moments in spacecraft coordinates from analysis of Panel 0 swings:

$$\text{SC A: } \vec{M} = [-0.82, 0.14, 0.99] \text{ Am}^2$$

$$\text{SC B: } \vec{M} = [-0.83, 0.25, 0.93] \text{ Am}^2$$

- Use dipole equation to compute magnetic field at location of EMFISIS DC Magnetometer:

$$\vec{B}(\vec{r}) = \frac{\mu_0}{4\pi} \left(\frac{3 \vec{r} (\vec{M} \cdot \vec{r})}{r^5} - \frac{\vec{M}}{r^3} \right)$$

$$\text{SC A: } \vec{B} = [1.81, -0.83, -2.19] \text{ nT}, B = 2.96 \text{ nT}$$

$$\text{SC B: } \vec{B} = [1.92, -0.31, -2.15] \text{ nT}, B = 2.90 \text{ nT}$$

- Both spacecraft meet requirement to contribute no more than 5 nT at the location of the EMFISIS DC Magnetometer with a 40% margin.
- The estimates for the SC magnetic moments obtained from the tests at APL and Astrotech agree within the measurement uncertainties.